



22 July 2020

Fairgrounds Improvements (Coliseum Roofing Repairs)  
Jackson, Mississippi  
G.S. #343-115



---

## ADDENDUM NO. 02

### NOTICE TO ALL DOCUMENT HOLDERS:

The following additions, deletions, changes and clarifications to the drawings and specifications are to be included as part of the Contract Documents.

### GENERAL NOTES

- ITEM NO. 01**      **Project Days:** The contract duration will be 15 months (465 calendar days) from the notice to proceed. The contract duration has been set to allow for any material delays or shortages due to COVID-19.
- ITEM NO. 02**      **GENERAL NOTE NO. 11:** Existing Lightning Protection system to be re-certified upon completion of the roofing work and/or ridge cap replacement.
- ITEM NO. 03**      **ALTERNATE NO. 5:** Add Snow Guard at perimeter of Coliseum, See Specifications

### SPECIFICATIONS

- ITEM NO. 04**      **Section 00300 – PROPOSAL FORM**  
**DELETE** specification section in its entirety and **REPLACE** with the enclosed section. REVISED to add calendar days and Alternate descriptions.
- ITEM NO. 05**      **Section 07 7100 – ROOF SPECIALTIES**  
**DELETE** specification section in its entirety and **REPLACE** with the enclosed section. REVISED to add information for snow guards.
- ITEM NO. 06**      **Section 07 7227 – FALL PROTECTION DEVICES**  
**ADD** specification section in its entirety with the enclosed section. ADD information for fall arrest system.
- ITEM NO. 07**      **Section 07 9200 – JOINT SEALANTS**  
**DELETE** specification section in its entirety and **REPLACE** with the enclosed section.

**ITEM NO. 08**      **Section 09 9113 – EXTERIOR PAINTING**  
**DELETE** specification section in its entirety.

**DRAWINGS**

**No ITEMS**      **None**

**QUESTIONS and ANSWERS**

1. Do you want butyl tape/ caulking at the patches or soldering the pop rivets? We recommend using caulk because of the movement in the copper. **Caulking or Butyl Tape is acceptable**
2. Do you want the flange for the repair caps caulked or soldered. We recommend Caulking because of the movement in the copper. **Caulking or Butyl Tape is acceptable**
3. Does anything get painted? There is a paint spec. **See Item No. 08**
4. For Alternate #4 we will need a fall arrest spec. **See Item No. 06**
5. Are we replacing all drain strainers on the copper roof or just the missing ones? **Replace ALL Strainers**
6. Is Fountain installing the new roof drains on the Modified Roofs and the strainers in their contract?  
**Lower roof drains are existing and not in contract, Drains at high roof are to be repaired per drawings.**
7. Are you wanting us to have the Lightning Protection System Re-Certified once we remove and replace the ridge cap where the post are mounted? **See Item No. 02**

Encl: Specifications (8.5x11):  
07.7100 Roof Specialties; 07.7227 Fall Protection Devices; 07.9200 Joint Sealants

Drawings (24x36):  
none

cc: All Document Holders  
File 0820.C2

