
ADDENDUM NO. 3

THIS ADDENDUM FORMS A PART OF THE CONTRACT DOCUMENTS AND
HEREBY MODIFIES THE ORIGINAL CONSTRUCTION DOCUMENTS DATED
JANUARY 21, 2021 RESPECTIVELY.


NAME OF COMPANY

BY

ELECTRICAL

Item #1 ELECTRICAL REQUIREMENTS

See attached items from Electrical Engineer.



END OF ADDENDUM NO. 3

ADDENDUM NO. 3

Project: Lauderdale County - Public Safety Building Selective Demolition

Division 26 Contractor shall provide the following work.

ELECTRICAL REQUIREMENTS

Contractor shall provide new electrical service to the building with the following characteristics to be left at the facility at the end of the demolition project. Electrical service shall included utility company compliant meter base, service mast & overhead service drop. Electrical service entrance equipment shall be minimum 200A, 240/120V, 1-Phase, 3-Wire with ground, 40-circuit panelboard with 200A2P main breaker, 20A1P circuit breakers as required for lighting and construction power. Location of electrical service and panelboard shall be coordinated with the Construction Manager prior to installation.

Contractor shall provide and connect LED construction lights with the following characteristics located throughout the space after demolition on 50' centers in both directions. Provide and connect 20A1P, 120V branch circuits using Type MC Cable as required to power lighting fixtures. Lighting fixtures shall be equal to Eiko Global Cat. No. LED150WTMP50K with 15000 lumen minimum output, 150W, 5000K color temperature, 80+CRI and chain-hanging provisions. On/off control of lights to be circuit breaker(s).

All work shall be provided in compliance with the National Electrical Code.

END OF REQUIREMENTS



02/19/2021