

Addendum No. 2

Date: September 1, 2017
PN: 16-019
Project: POLICE & COURT SERVICES
RENOVATION & EXPANSION
110 & 112 BROOKS STREET
TOWN OF PELAHATCHIE, MS 39145
Bid Date: **September 12, 2017; 2:00 p.m.**
Architect: J. Scott Williams Architect, PLLC.
176 River Park Drive
Jackson, MS 39202
Phone: (601) 209 7334

NOTE TO BIDDERS: This Addendum, consisting of 2 pages and 0 attachments, is hereby made part of the Contract Documents. Wherever the original Contract Documents are inconsistent herewith, provisions of this Addendum will govern.

Specifications:

- 1. PRE-BID ON-SITE MEETING WILL BE SEPTEMBER 7, 2017 (Thursday) AT 10:00 AM LOCATED AT 110 & 112 Brooks Street, Town of Pelahatchie, MS 39145.**
- 2. SECTION 00100 - INSTRUCTIONS TO BIDDERS – SECTION 1.8 CONTRACT:** Delete Paragraph E.Liquidated Damages for Failure to Enter into Contract in its entirety.
- 3. SECTION 01020 - ALLOWANCES – SECTION 1.2 SCHEDULE OF ALLOWANCES:** Addition of Item “C. Include in the alternate 1 bid for inclusion in the contract sum, the amount \$8.800.00 for the purchase of Interior Signage.

4. **SECTION 07530 – FLEXIBLE SHEET ROOFING SYSTEM– PART 1.01 GENERAL ITEM “A”.** **Scope:** 1. Contractor shall furnish and install a 50 mil. Ketone Ethylene Ester (KEE) or PVC membrane roof system that has a reinforced fabric weft-inserted scrim).
5. **SECTION 07530 – FLEXIBLE SHEET ROOFING SYSTEM– PART 2.01, Materials, Item “A” General:** 1. Roof system specification based on Fiber-Tite Roofing System or EQUAL; white color, all components.
6. **SECTION 08560 – STAINLESS STEEL FRAME BULLET RESISTANT TRANSACTION WINDOW – SECTION 2.02 MATERIALS:** Revised Item “C” and revised as follows: “C. Glazing: The glazing must be in accordance with U.L. 752 testing standards Level 3: LP 1250 composed of an acrylic interlayer with polycarbonate cap sheets with a thickness of 1.25”.
7. **SECTION 09640 - WOOD FLOORING – SECTION 3.3 PROTECTION:** Addition of Builder Board to Item “A” and revised as follows: Protect installed wood flooring during remainder of construction period with covering of heavy craft paper, Builder Board, or other suitable material.
8. **SECTION 10400 – INTERIOR SIGNAGE –** Remove the Section in its entirety.
9. **SECTION 10410 – EXTERIOR SIGNAGE –**Clarification of Part1-General item 1.2 “The scope of work required shall be to provide a new metal cast individual letter of 12” height, font selected by Architect, brushed rubbed bronze finish raised 1” from mounting surface. As shown in drawings.
10. **SECTION 00100 - INSTRUCTIONS TO BIDDERS – SECTION 1.8 CONTRACT:** Delete Paragraph E.Liquidated Damages for Failure to Enter into Contract in its entirety.

Electrical:

1. **SECTION 16910,** Paragraph 2.3 IP Video Management System: System shall be furnished with (2) 4 TB Hard Drives.
2. **Axis shall be an acceptable CCTV manufacturer.**