

ADDENDUM NO. ONE (1)

July 3, 2019

Owner: City of Madison
Project: Quail Run Subdivision Low Pressure System

The following items are to be modified in the Contract Documents and Specifications for the referenced Project:

1.0 Technical Specifications:

1. Section 02563 Force Main: Delete Section 3.12.
2. Section 02270 Erosion Control: Add the following to Section 1.1, Paragraph C:.

The contractor will be responsible for developing a Stormwater Pollution Prevention Plan (SWPPP), if required by the state of Mississippi.

3. Section 11307 Grinder: Add the following to Section 2.13:

D. Additional power and/or control cord length, if required, shall be provided at no additional cost to the Owner.
4. Section 11307 Grinder: Add the following to Section 2.5, Paragraph E:

Additional basin depth, if required, shall be provided at no additional cost to the Owner.

2.0 Contract Drawings:

1. Sheet G0.01: Replace General note No. 20 with the following:

Install Force Main underneath all driveways and streets by boring or directionally drilling, unless otherwise shown or by engineer's written approval. Contractor shall repair any driveways as a result of the project at no additional cost to the owner.
2. Sheet C1.08: Change 2" force main at STA 50+20 to 3" Force main in Profile view.
3. Sheet C1.09: Change 2" Force Main to 3" Force Main in Profile view.


4. Sheet C1.10: Change 2" Force Main to 3" Force Main in Profile view.
5. Sheet C2.02: Add the following note:
 4. Anti-Flotation Collars are required on fiberglass basins. Contractor shall install according to the basin manufacturer's recommendations.

3.0 Clarification:

1. No formal project sign is required.
2. Uncased bores will be measured and paid for under Force Main bid item.
3. Native material can typically be used for pipe bedding unless otherwise directed by the Engineer.
4. Solid sod is required in all areas for restoration unless otherwise directed by the Engineer.
5. Electrical connections from the power supply to the control panel will be provided by others.
6. Contractor can elect to directional drill all pipe using HDPE pipe, except jack and bore items.
7. Solvent weld joints are not acceptable on buried piping.
8. Air release valves shall be installed in precast concrete manhole cone sections.

This Addendum is to be acknowledged by the Bidder on the Bid Form.

Pickering Firm, Inc.


Dan M. Townsend, P.E.