

June 28, 2022

ADDENDUM NUMBER FIVE (5)

Project: SCSD ESSER Package 1  
Smith County School District  
PN: 21092

FROM: Dean Architecture, P.A..  
661 Sunnybrook Road, Suite 140  
Ridgeland, MS 39157  
(601) 939-7717

The following additions, changes, clarifications and/or substitutions to the Project Drawings as indicated, are hereby made a part of the Contract Documents. Acknowledge receipt of this Addendum by inserting its number and date in the Proposal Form where indicated.

Mechanical

**Item #1:** Sheet M202: Remove existing MAU-1 and replace with new MAU-1 as follows:  
Greenheck model DGX-P124-H32-MF, 9,500 cfm @ 1.5" e.s.p., 10 hp, 460/3 phase, 18.4 MCA, 535,000 BTU/HR max. input, 492,500 BTU/HR max. output, electronic modulating gas valve.  
Electrical notes: Disconnect existing MAU-1; connect new MAU-1 as follows:  
Demolish existing circuitry to existing unit. Provide (3) #10s, (1) # 10 ground in existing conduit. Replace existing circuit breaker with new 30/3 breaker.

END OF ADDENDUM FIVE (5)

Dean Architecture

  
Kenneth A. Oubre, AIA, Principal



PLEASE ATTACH THIS ADDENDUM TO THE INSIDE FRONT COVER OF EACH SET OF SPECIFICATIONS.